

DOE Manual Min. Req't #	Description	Title 20 Requirements			SMP Requirements	
		Within Special Stormwater Districts* but outside NPDES Phase II areas	Outside of Special Districts and NPDES Phase II (Low/Medium/High use intensity)	NPDES Phase II	Existing	Proposed
1	Stormwater Site Plan	≥ 500 sf	≥ 7,000/≥ 4,000/≥ 2,000	≥ 2,000 sf	≥ 2,000 sf	Required
2	Construction SWPPP	Required	Required	Required	Required	Required
3	Source Control	Required	Required	Required	Required	Required
4	Preserve Natural Drainage	≥ 500 sf or 50% renovation	≥ 7,000/≥ 4,000/≥ 2,000	Required	Required	Required
5	On-site stormwater management (infiltration or dispersion)	Required	N/A / ≥ 4,000/≥ 5,000	≥ 2,000 sf	≥ 2,000 sf	Required
6	Treatment (water quality)	Required	N/A / ≥ 4,000/≥ 5,000	≥ 5,000 sf	≥ 5,000 sf	Required
7	Flow Control (water quantity)	Property < 2 acres meeting MR1 where project increases the 24-hour, 100-year peak flow rate by ≥ 0.1cfs; provide detention	N/A / ≥ 4,000/≥ 5,000	≥ 5,000 sf	≥ 5,000 sf	Required
8	Wetland Protection	≥ 500 sf or 50% renovation	≥ 7,000/≥ 4,000/≥ 2,000	≥ 2,000 sf	≥ 2,000 sf	Required
9	Operation and Maintenance (if stormwater facility required)	Required	Required	Required	Required	Required

\* Birch Bay, Drayton, Lake Padden and Lake Samish watersheds

\*\* UGAs & Lake Whatcom Watershed